



ESS
bilbao



**EUROPEAN
SPALLATION
SOURCE**

The final design and manufacturing process for the ESS Monolith Vessel

F. Sordo¹ , J. Osoro² , I. Arrillaga² , C. Perez³ , M. Andersson⁴ , S. Ghatnekar⁴

**Consorcio ESS-BILBAO¹ , AVS+CADINOX²
Bureau Veritas³ , European Spallation Source ERIC⁴**

October 16th, 2019

Table of contents

- 1 Introduction
- 2 Critical design review
- 3 Redesign work
- 4 Manufacturing process
- 5 Conclusions

Introduction

Introduction

ESS project

ESS is an going project to build a 5 MW spallation source in Lund (Sweden) with a total budget $\sim 1800Me$. There is 17 Eu countries that take part in the project. Spain contributes with 3% of the total construction cost total construction cost.

ESS construction site (View in March 2019)




ESS-BILBAO Consortium

Role and functions


- ESS-Bilbao is public consortium between Spanish Central Government and regional government of Vase Country region.
- ESS-BILBAO has been nominated as Spanish representing entity for ESS operational phase.
- Staff of 50 scientists & engineers.
- The collaboration between ESS-Bilbao and IFN started on 2009. ESS-bilbao Target division is working at IFN facilities in Madrid.
- On December 2014, ESS-Bilbao was chosen as ESS partner for Monolith Vessel.
- KO meeting held on December 2015.
- **On February 2017, Critical design review for the Lower and medium vessel.**
- Contract for LMV manufacturing awarded on September 2018 to AVS+CADINOX.
- Manufacturing is on going.

Introduction

ESS Monolith Vessel on ESS target station



ESS Target Station





Monolith Vessel

Monolith Vessel

- Helium compatible
- Vacuum compatible
- 40 year life time
- Safety related equipment
- RCC-MR_x N3Rx
- ϕ 6 x 12 m
- 75000 kg mass

Introduction

ESS Monolith Vessel on ESS target station





Critical design review

Critical design review

Design analysis

The design proposed on CDR (July 2017) was optimized according to several load cases (vacuum, 2 bar overpressure, seismic events ...). The CDR was approved on late 2017 but due to administrative reasons the Call for tender was not published until Summer 2018.

Buckling elastoplastic analysis for a 20 mm preformed geometry





Critical design review

Design analysis

The design proposed on CDR (July 2017) was optimized according to several load cases (vacuum, 2 bar overpressure, seismic events ...). The CDR was approved on late 2017 but due to administrative reasons the Call for tender was not published until Summer 2018.

Seismic events analysis.




Critical design review

Design analysis

The design proposed on CDR (July 2017) was optimized according to several load cases (vacuum, 2 bar overpressure, seismic events ...). The CDR was approved on late 2017 but due to administrative reasons the Call for tender was not published until Summer 2018.

Seismic events analysis.




Critical design review

Manufacturing plan

The propose manufacturing plan considers to build the vessel is a single piece, cutted after the pressure test and ship to Lund in tow sections. This proposal includes significant on site work for bevel preparation and final welding.

Assembling scheme





Redesign work

Redesign work

Contract awarded to AVS+CADINOX

On September 2018, the manufacturing contract was awarded to AVS+CADINOX. The new manufacturing team adapted the design to his technical capacities in order to minimize on site work. Its facilities has a limitation in the maximum height of the vertical lathe and thus the vessel was split in two sections flange connected.

CADINOX vertical lathe. Maximum height ~ 3 m




**Bolted connection
+ sealing weld on site**

Redesign work

Contract awarded to AVS+CADINOX

On September 2018, the manufacturing contract was awarded to AVS+CADINOX. The new manufacturing team adapted the design to his technical capacities in order to minimize on site work. Its facilities has a limitation in the maximum height of the vertical lathe and thus the vessel was split in two sections flange connected.

CADINOX vertical lathe. Maximum height ~ 3 m




Redesign work

AVS+CADINOX change requested

The thickness of the flanges and lateral walls were increased to withstand the loads produced in the machining process. The connection between both sections relies on bolted flange seal welded on site.

Vessel split in two sections flanged




Redesign work

AVS+CADINOX changes requested

The thickness of the flanges and lateral walls were increased to withstand the loads produced in the machining process. The connection between both sections relies on bolted flange seal welded on site.

Vessel split in two sections flanged





Redesign work

AVS+CADINOX changes requested

The thickness of the flanges and lateral walls were increased to withstand the loads produced in the machining process. The connection between both sections relies on bolted flange seal welded on site.

Vessel split in two sections flanged



Redesign work

Welding book

The monolith have to be compatible with nuclear design rules ($RCC - MR_x N3R_x$) and vacuum. This limits the welding technologies for TIG (141) which is not feasible for large components. The solution is to combine TIG (141) welding for root passes facing the vacuum and submerge arc for the bulk (121)

WPQR and welding book

ESS WPS n°	Tipo de soldadura	Material base	Proceso soldadura	Automatizacion	Espesores (mm)	
		PQR			PQR	Rango cualificacion
001	<u>BW-chapa</u>	X2CrNiMo17-12-2 (316L)	141 (TIG)	Manual	20	10-40
002	<u>FW</u>	X2CrNiMo17-12-2 (316L)	141 (TIG)	Manual	20	3-40
003	<u>FW</u>	X2CrNiMo17-12-2 (316L)	141 (TIG)	Manual	T1=6 / T2=25	T1=3-12 / T2=3-50
004	<u>BW-chapa</u>	X2CrNiMo17-12-2 (316L)	141 (TIG)	Manual	2	1-4
005	<u>BW-tubo</u>	X2CrNiMo17-12-2 (316L)	141 (TIG)	Manual	2,9 (D26,7)	1,45-5,8 (D≥13,35)
006	<u>BW-tubo</u>	X2CrNiMo17-12-2 (316L)	141 (TIG)	Manual	25 (D450)	12,5-50 (D≥225)
008	<u>BW-chapa</u>	X2CrNiMo17-12-2 (316L)	141 (TIG)	Manual	40	20-80
009	<u>BW-chapa</u>	X2CrNiMo17-12-2 (316L)	121(SAW)	Semi-automático	30	15-60
011	<u>BW-chapa</u>	X2CrNiMo17-12-2 (316L)	141 (TIG)	Semi-automático	40	20-80

Manufacturing process

Manufacturing process

Raw material provided by Outokumpu

The raw material is composed by ~ 45 tonnes of plates with thicknesses from 25 to 90 mm and more than 4 tonnes of filled material for TIG and Submerged arc welding processes. The production takes more 20 weeks an the material was delivery in July 2019.

Raw material and filled material (~ 4 tones) delivery



Plates delivery



Dimensional control

Manufacturing process

Raw material provided by Outokumpu

The raw material is composed by \sim 45 tonnes of plates with thicknesses from 25 to 90 mm and more than 4 tonnes of filled material for TIG and Submerged arc welding processes. The production takes more 20 weeks an the material was delivery in July 2019.

Raw material and filled material (\sim 4 tones) delivery



Welding consumables







Quality labels (TIG wire)

Manufacturing process

Bottom plate

The bottom plate is assembled on three sections welded (60 mm thickness). On top of this structure the central supports are welded (filled non continuous welding).

Bottom plate (100 mm submerged arc (121) + TIG (141))




Manufacturing process

Bottom plate (100 mm submerged arc (121) + TIG (141))

WMAP	WPS	Welding detail according Boiler drawing N053.010.001_SHEET 1-4			
WMAP-5078/18-1	100.18				
	<table border="1"> <thead> <tr> <th>Joint design</th> <th>Welding sequence</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> </tr> </tbody> </table>		Joint design	Welding sequence	
Joint design	Welding sequence				


WS1-WS4 Submerged arc (121)
WS5 TIG semiautomatic (141)





Bottom plate welding completed

Manufacturing process

Bottom plate (100 mm submerged arc (121) + TIG (141))



Support blocks





Spot TIG welding (141)

Manufacturing process

Medium vessel wall

WMAP	WPS	Welding detail according Boiler drawing N053.010.002_SHEET 1-2			
WMAP-5078/18-6	200.1				
	<table border="1"> <thead> <tr> <th>Joint design</th> <th>Welding sequence</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> </tr> </tbody> </table>		Joint design	Welding sequence	
Joint design	Welding sequence				



Conclusions

Conclusions

Main remarks

- The design has been adapted to supplier technical capacities.
- Raw material reception was completed in June 2019
- Welding qualification processes were completed on August 2019.
- Manufacturing is on going and the component will be delivery in Q1 2020.