

Testing Frozen-Spin HD with electrons at Jefferson Lab

- status update -

Xiangdong Wei

Jefferson Lab



2019 Workshop on Polarized Sources, Targets, and Polarimetry

09/23/2019-09/27/2019



JLab - HDice Group:

G. Dezern, C. Hanretty, T. Kageya, M.M. Lowry, A. M. Sandorfi, and X. Wei

JLab - Injection Group:

J. Grames, S. Gregory, M. Poelker

University of Connecticut:

T. O'Connell, K. Wei

Universita di Ferrara and INFN di Ferrara:

L. Barion, M. Contalbrigo

Universita di Roma "Tor Vergata" and INFN-Sezione di Roma2:

A. D'Angelo

- $\vec{H}\vec{D}$ lifetimes with photon beams ~ 2 years :
 - PRL **102** (2009) 172002; PRL **118** (2017) 242002; ...
 - NIM **A737** (2014) 107; NIM **A815** (2016) 31; ...
- next goal – viable transverse frozen-spin target with electron beams
- electron *experiments with transverse polarization* :

	PAC 39	PAC 41	
	<u>rating</u>	<u>decision</u>	<u>impact</u>
◊ SIDIS, C12-11-111, Contalbrigo,...	A	C1	★
◊ dihadron production, PR12-12-009, Avakian,...	A	C1	★
◊ DVCS, PR12-12-101, Elouadrhiri,...	A	C1	★

C1 \Rightarrow successful demonstration of viable performance in an eHD test

★ all transverse experiments designated as ***High Impact*** for Hall B at JLab

- challenge: transverse holding fields bend electrons into the detector !
- mitigation: small $B \cdot dL$ \Leftrightarrow **frozen-spin HD**

Mechanisms for beam-induced depolarization:

I. beam-heating

- heat ➤ reduce T1s of HD
- solution: keep HD cold to stay in frozen-spin mode
 - ↔ new target cells to optimize the cooling
 - ↔ new fast raster to minimize the dwell time


II. Hyperfine mixing

- $\vec{\mu}(e)$ opposite to $\vec{\mu}(p)$ ➤ polarized electrons mix and dilute H polarization
- solution: flip H spin against field, so that e and H polarizations are parallel

III. Radiation damage

- beam ionization ➤ chemical changes that could bring HD out of frozen-spin state
- expected to be temperature dependent ↔ needs detailed study

Electron energy loss in 5 cm of HD:



⇒ loss dominated by bremsstrahlung


- deposition dominated by Møllers
 $\sigma_{\text{Møller}} \sim (1 + 1/\gamma)^2$
~ independent of beam energy

⇒ deposition: $2 \text{ MeV/e}^- = 1 \text{ mW}/\frac{1}{2} \text{nA}$
~ independent of beam energy


⇒ 10 MeV beams will test the HD performance at 10 GeV !

Upgraded Injector Test Facility (UITF)

Test Lab




Thomas Jefferson National Accelerator Facility




- parity-quality beams

Energy:	5-10 MeV; $\sigma E/E < 10^{-3}$
Current:	100 pA-5 nA CW 100 nA Tune-mode
Size:	$50 \mu\text{m} < \sigma_{x,y} < 150 \mu\text{m}$
Stability:	within $\sigma_{x,y}$
Beam Halo:	$< 10^{-4}$
Polarization:	> 70%
Helicity flip:	1-30 Hz




- ↔ qualify CEBAF injector components
- ↔ study HD characteristics with 10 MeV electrons

Tuning Beam Spot inside IBC



- solenoid fields focus at 10 MeV \Leftrightarrow energy tuned to place node at the HD surface.
 => possible to tune the beam energy and/or solenoid field to expose HD target uniformly.


X. Wei



- 10 MeV energy loss \sim same as 10 GeV,
but beam optics is *VERY DIFFERENT*
- *solenoid edge focusing*
creates nodes through IBC


**HD
target**

**target
solenoid**



UITF beam transport through the IBC


- pencil beam offset by 12mm makes 3 revolutions through the IBC





C. Hanretty




- adjust solenoid fields and UITF energy to create ~ parallel beams through the HD target

$$E_{UITF} = 9.5 \text{ MeV}$$





Rastered Beam
($E = 9.5$ MeV)



*upstream
face of HD*



Injector:

- 200 keV beam up to dump before $\frac{1}{4}$ CryoModule ✓





¼ Cryo-module (2 + 7 cavities):

- cooled to 4K with LHe from CTF ✓
- *PSS systems certified* ✓
- *Klystrons commissioned* ✓
- *high power RF tests complete* ✓
 ⇒ *max gradients w/o field emission*
 sufficient for 10 MeV ✓
- *parked until reviews complete*



$\frac{1}{4}$ Cryo-module (2 + 7 cavities):

- cooled to 4K with LHe from CTF ✓
- *PSS systems certified* ✓


	Activity Name	Notes	2019						
			Mar	Apr	May	Jun	Jul	Aug	Sept
93	Approvals for low-current UITF OPS	...							
94	SCMB evaluation of PSS BCM								
95	UITF Accelerator Operations Directive								
96	Conduct of Operations Review								
97	Accelerator Readiness Review								
98	HDice experimental Readiness review								
99			March	April	May	June	July	August	September



sufficient for 10 MeV ✓


- parked until reviews complete

UITF status – Cave 2



Cave 2 beam line:

- *99% beam line components in place up to HDice ✓*





Cave 2 beam line:

- 99% beam line components in place up to HDice ✓
- new fast spiral raster installed ✓
 - circular pattern: 20 KHz FM; 1 KHz AM
 - tested I CEBAF injector




New Fast Raster (C. Cuevas, W. Gunning, ...)






Sub-nA BPMs - Rogowski coils (K. Wei with Jülich)



Cave 2 beam line:

- 99% beam line components in place up to HDice ✓
- new fast spiral raster installed ✓
 - circular pattern 20 KHz FM; 1 KHz AM
 - tested I CEBAF injector
- new sub-nAmp BPMs in development
 - “Rogowski coils” (after COSY / Jülich)
 - sensitivity ~ 600 pA and dropping...







In-Beam Cryostat (IBC):

- *1.25 Tesla and 50 mK*
- *serviced, installed and ready to be cooled*
- *NMR is used for polarization monitoring*


Halo Counter




Halo counter holder 3D render




Halo counter holder 3D render



Halo counter holder 3D render



Halo counter holder 3D render



Halo counter scintillators box


**IBC
Halo Counter**

**IBC
Snout**

Delivery: Oct. 2019

X. Wei

Down Stream Solenoid and Beam Dump



Dump Solenoid delivery: End of Sep. 2019

Vacuum Can with Beam Dump delivery: December 2019

X. Wei



eHD test schedule at the UITF



- *gun performance at CEBAF – replacements come from UITF*
- *UITF $\frac{1}{4}$ CM is cooled by LHe from the Cryogenic Test Facility (CTF) liquifier*
 - *TestLab demand exceeds CTF capacity*
 \Leftrightarrow *beam-line commissioning and HD studies require ~80 days of LHe to $\frac{1}{4}$ CM*
- *NCLS-II cryomodules are routinely stored on the roof of cave-2*
 - *cave-2 roof must be removed for target transfers (~ 10 times)*
- *$\frac{1}{4}$ CM will be moved to CEBAF on May 6, 2020*
 \Leftrightarrow *HD testing must be completed by then !*