Development of the CSNS Target Plug

Shaohong Wei, Ruiqiang Zhang, Quan Ji, Xunjun Jia Chinese Spallation Neutron Source





Outline

- 1. Status of CSNS Target System
- 2. Design of Target Plug
- 3. Introduction of fabrication
- 4. Summary



1. Status of CSNS Target System

- (1) Fabrication of all the components has been finished. (Target Plug: Jan. 2016 / Target Trolley: Jul. 2016)
- (2) Acceptation tests have been done. (Including Ta cladding performance, seal performance, position accuracy measurement...)
- (3) In-site installation began in Sept. 2016. Most of the components have been installed. Will be finished in Nov. 2016 and then in-site test will be started. (Trolley rails, fixed shielding blocks, moveable shielding blocks, transmission system, etc., installed)





Target Plug Target Trolley



In-site installation



Hot cell



Trolley rail assembly (17m)




Fixed shielding blocks



Moveable shielding blocks




Trolley with target support




Insert Helium Vessel port



2. Design of Target Plug



Schematic layout of CSNS facilities




Position where Target system installed

CSNS primary parameters in baseline


Project phase	I
Beam ave. power, kW	100
Proton energy, GeV	1.6
Ave. current, Ι, μΑ	62.5
Repetition rate, Hz	25
Proton per pulse, 10 ¹³	1.63
Pulse length, ns	<500
Linac energy, MeV	80
Linac peak current, mA	15
Target material	Tungsten
No. Moderators	3
No. neutron instruments	3



Target plug is comprised of Tungsten Target, Target Vessel and Rear Block.







Tungsten(Ta-cladded) Target

Number of target blocks: 11

Cross section: 170mm*70mm,

Thickness: 23~80mm


Density of tungsten:

Thickness more then 37mm: >18.6g/cm³

Thickness less then 37 mm: $>19.2 \text{g/cm}^3$



Thermal design



Coolant: Heavy water

Inlet temperature: 30°C Pressure: 0.4MPa

Flow rate: 140L/min


Calculation results

Max temperature ($^{\circ}$ C)				Cooling water		
Target blocks	Surface of target blocks	Target vessel	Target window	Pressure drop (kPa)	Temperature rise (°C)	Max velocity (m/s)
180.05	125.16	85.90	60.80	13.94	6.50	3.66



Seal design


- ♦C-ring is adopted to seal cooling water;
- ◆Seal rings can be replaced along with Target Plug;
- ◆Intermediate flange is designed in case the sealing surface damaged







Self-alignment structure

- Three guide pins for guiding direction when
- Target Plug is aligned to the support on trolley
- ➤ Double inclined planes for accurate position








Precise position and good seal performance can be achieved when bolts tightened.




Structures related to Remote handing




A special lifting tool is developed for target replacement operation.

Two tungsten counter weight was applied to adjust gravity center of Target Plug






Operation to replace Target Plug





1: Loosen the blots

2: Hoist the lifting tool and align to Target Plug



3: Hoist Target Plug by lifting tool



3. Introduction of fabrication

Tungsten target with tantalum cladding



Before HIP

Sample for testing



After HIP

Target material: tungsten

Cladding material: tantalum


Tantalum thickness: 0.3 ± 0.05 mm

HIP process:

T---1550 °C

P---150MPa


Holding time----2hours



Target blocks



W-Ta interface microstructure morphology




There is no obvious defect in the W-Ta interface



Tensile strength test

Samples	The tensile strength (MPa)	average value (MPa)	
1	61. 04	65. 09	
	66. 03		
	68. 22		
2	79. 47		
	Equipment failure	77. 24	
	75. 0		
3	78. 95	72. 87	
	78. 46		
	61. 21		




Conclusion: All samples tensile strength is above 60MPa




Assembling

Target vessel and vessel cover welded by electron beam welding.



Target blocks placed in target vessel



Target finished assembling



Target after EB welding





Target Plug is ready for in-site installation!



4. Summary

- (1) Fabrication of CSNS Target Plug has been finished (Jan. 2016);
- (2) Target plug will be installed on the Target Trolley in Nov. 2016;
- (3) The first beam on Target will be in Sept. 2017.





